



Fence World

202 Corpus Christi
Laredo, TX 78040

Phone: 956-796-0102



Fence World

May 22, 2014

**Webb County C.C.A.
El Aguila Rural Transportation
C/O Roberto Martinez
4801 Daughtery
Laredo, TX 78041
T: (956)722-6100
F: (956)726-4524
M : (956)237-9802
EMAIL: romartinez@webbcountytexas.gov
Project: Ornamental Iron Fence**

Scope of Work: Labor & Materials for Installation of 410' lineal feet of 6' high in total, combination of 4' Ornamental Iron panels on top of 24" base with concrete footing. Fabrication & Installation of 25' x 6' high Sliding Gate that will run on Steel V Track.

Construction of 24" Base & Footing will consist of digging 1'x1' trench set in 4-1/2" rebar construction with 8" steel stir ups @ 16 spacing and fill in with concrete. Lay 3 rolls of 8" cinder block with steel reinforcement @ 12' spacing and seal in with concrete in order to form a cap on top. Prepare base for stucco finish all around.

Style of Fence: Steel (SQ. Tubing)

**2 1/2"x2 1/2" – Posts @ 8' spacing with caps
3-1 1/2"x1 1/2" Horizontal Rails
3/4"x3/4" Verticals @ 4" spacing with caps
2"x2" - Gate Frame
Prime & Painted Black**

Supply & Install 16 concrete tire stops!

Subtotal: \$26,765.00

Accepted: _____

Prepared By: Eben Martinez

Laredo TX. 78041

(956)727-2881

SOLD TO:

Name : El Aguila Transportation
Address: 4801 Daughtery
Laredo, TX 78041
E-mail: romartinez@webbcountytx.gov
ROBERTO MARTINEZ JR.
Ph# 956-722-6100

DATE June 12, 2014
ORDER NO. 7262755



1	410' Linear feet 6' high: INCLUDES Sq Tubing Post 2 1/2 x 2 1/2 Every 10' Feet Sq Tubing 1 1/2 x 1 1/2 on top and bottom Sq Tubing 3/4 Sliding gate 25'x 6' will run on steel track frame 2x4 Wheels and Rollers Primer and Painted Black	\$ 15,960.00	\$ 15,960.00
1	410' Linear feet Cinder Block: INCLUDES 24" Base and footing: 1'x 1' Trench set in 4 1/2 rebar const with 8" steel stir ups. 16' Spacing and filled with concrete. 3 rows of 8' Cinder block with steel reinforcecent @ 12' Spacing filled in with concrete. Base for stucco finish all around.	\$ 10,400.00	\$ 10,400.00
17	Standard concrete barriers for parking area reinforcement 1/2	\$ 105.00	\$ 1,785.00
		SUBTOTAL	28,145.00
		TAX	
		FREIGHT	
			\$28,145.00 PAY THIS AMOUNT

DIRECT ALL INQUIRIES TO:
Ramon Torres Sandra C. Torres
(956)727-2881 (956) 269-4346
email:rstorres.services@gmail.com

MAKE ALL CHECKS PAYABLE TO:
RS Torres Services