

Flag Systems
 2300 Valley View Lane #109
 Dallas, TX 75234
 972-607-0958
 www.TheDallasFlagStore.com

Estimate

| | |
|----------|------------|
| Date | Estimate # |
| 1/9/2020 | 4696 |

| |
|---|
| BILL TO |
| Webb County Courthouse 1100 Houston Street Laredo, Tx 78040 |

| |
|----------------|
| Project |
| |

| Item | Description | Qty | Rate | Total |
|---------------------------|--|-----|----------|----------|
| Independence 35x6x156 SAT | 35' Exposed Height Satin Finish 2-Piece 38.5' Overall Length 6" Base Diameter .156" Wall Thickness 116 mph Unflagged Wind-speed 90 mph Flagged Wind-speed Stainless Steel Cable Based Internal Halyard System with a Flush Fitting Door. Standard Fittings: Cone -Style Revolving Truck Assembly with Gold Anodized Ball, Stainless Steel Gear-less Winch, Winch Handle, Smooth Flush Locking Door Configuration, Cast Aluminum Swivel Winch Plate, Access Hole Button, Stainless Steel Aircraft Cable, Leader Cable, Stainless Steel Flag Snaps, Nylon Coated Steel Counterweight, Retainer Ring, Stainless Steel Connecting Links, Flash Collar (Decorative Base Plate), and Corrugated Steel Ground Sleeve Assembly. 1 Year Warranty | 2 | 4,125.75 | 8,251.50 |

| | |
|-------------------------------------|--------------------------|
| **50% deposit due upon scheduling** | Subtotal |
| | Sales Tax (8.25%) |
| | Total |

Flag Systems
 2300 Valley View Lane #109
 Dallas, TX 75234
 972-607-0958
 www.TheDallasFlagStore.com

Estimate

| | |
|----------|------------|
| Date | Estimate # |
| 1/9/2020 | 4696 |

| |
|---|
| BILL TO |
| Webb County Courthouse 1100 Houston Street Laredo, Tx 78040 |

| |
|----------------|
| Project |
| |

| Item | Description | Qty | Rate | Total |
|------------------------------|--|-----|----------|----------|
| Independence 40x7x156 SAT | 40' Exposed Height Satin Finish 2-Piece 44' Overall Length 7" Base Diameter .156" Wall Thickness 122 mph Unflagged Wind-speed 90 mph Flagged Wind-speed Stainless Steel Cable Based Internal Halyard System with a Flush Fitting Door. Standard Fittings: Cone -Style Revolving Truck Assembly with Gold Anodized Ball, Stainless Steel Gear-less Winch, Winch Handle, Smooth Flush Locking Door Configuration, Cast Aluminum Swivel Winch Plate, Access Hole Button, Stainless Steel Aircraft Cable, Leader Cable, Stainless Steel Flag Snaps, Nylon Coated Steel Counterweight, Retainer Ring, Stainless Steel Connecting Links, Flash Collar (Decorative Base Plate), and Corrugated Steel Ground Sleeve Assembly. 1 Year Warranty | 1 | 5,159.00 | 5,159.00 |
| American Flag Nylon 8' x 12' | US 8'X12' Nylon | 1 | 159.00 | 159.00 |
| TX Nylon 6'X10' | Texas 6'X10' Nylon | 1 | 89.00 | 89.00 |
| DF Custom Flags 6'X10' | Double Sided 6'X10' | 1 | 479.00 | 479.00 |

| | |
|-------------------------------------|--------------------------|
| **50% deposit due upon scheduling** | Subtotal |
| | Sales Tax (8.25%) |
| | Total |

Flag Systems
 2300 Valley View Lane #109
 Dallas, TX 75234
 972-607-0958
 www.TheDallasFlagStore.com

Estimate

| | |
|----------|------------|
| Date | Estimate # |
| 1/9/2020 | 4696 |

| |
|---|
| BILL TO |
| Webb County Courthouse 1100 Houston Street Laredo, Tx 78040 |

| |
|----------------|
| Project |
| |

| Item | Description | Qty | Rate | Total |
|--------------------|--|-----|----------|----------|
| Installation Fee | Flag Systems Professional Installation Includes: materials, equipment, labor, pole transport 1 year warranty | 1 | 3,100.00 | 3,100.00 |
| Trip Charge | Trip charge (one-way) to: 1100 Houston Street Laredo, Tx 78040 | 450 | 1.75 | 787.50 |
| Lights | 100 Watt Flagpole Light | 3 | 425.00 | 1,275.00 |
| Light Installation | Lighting Installation per hour (minimum 4 hours, Pricing subject to change) | 4 | 175.00 | 700.00 |

| | | | |
|-------------------------------------|--|--------------------------|-------------|
| **50% deposit due upon scheduling** | | Subtotal | \$20,000.00 |
| | | Sales Tax (8.25%) | \$0.00 |
| | | Total | \$20,000.00 |