

5/3/18 item #7

SimplexGrinnell

A business unit of Tyco Fire & Security

BE SAFE.

SimplexGrinnell LP
1070 Arion Circle #102
San Antonio, TX 78216
Phone 210 402-6311
Fax 210 402-6195
<http://www.simplexgrinnell.com>

Applicable use or sales tax is excluded from this proposal.

Webb County Justice Center Fire Alarm System Scope of Work

SimplexGrinnell will provide a new Simplex addressable fire alarm system at the subject facility in accordance with the following:

All pricing is based on **Replacing the existing Fire Alarm Control panel and Initiating devices** with the following clarifications:

- All notification devices and cabling will remain and be connected to new system (AV's and Strobes)
- Existing Notification power supplies will remain and reconnect to system. New back batteries will be installed in each NAC power supply
- This is a device for device replacement of Fire Alarm control panel, Annunciator, Pull Stations, Smoke Detectors, Heat detectors, Duct detectors, Monitor modules and relay modules not a code upgrade.

The quoted Fire Alarm price includes:

1. Fire alarm equipment
2. Shop drawings and submittals
3. Prevailing wage rate
4. System programming & System testing
5. Laredo permit application
6. Laredo FM inspection during normal working hours
7. Project close-out documentation
8. SimplexGrinnell one-year equipment warranty

Please note the following exclusions:

- Raceway, including conduit where required and standard device back boxes
- Supply & installation of fire wrap, fire caulking or any other fire resistive materials required for installation of conduit, standard back boxes, and/or SG provided FA panel back boxes.
- Smoke Control panel and/or smoke control system interface.
- 120VAC work
- Applicable taxes
- Additional cost or expenses for special personal back ground checks above standard SG requirements.
- Cutting, patching, painting or re-surfacing of walls or ceilings
- Remote monitoring of the fire alarm system via central station
- After-hours or weekend or holiday work.
- 3-D BIM modeling of shop drawings.

- Support of third party certification & testing and all liability for costs to others associated with third party certification & testing.
- ~~CI Cabling - It is understood that where required by code a 2hr rated fire protective enclosure will be provide so as to install standard fire alarm cable. If a 2hr rated fire protective enclosure cannot be provided and 2hr rated Electrical Circuit Integrity (CI) fire alarm cable is required this will be a cost in addition to this proposal price~~

CAD Drawings

CAD drawings must be provided for our use in shop drawing preparation at no charge. Please allow 4-6 weeks from our receipt of an executed subcontract or purchase order for shop drawing completion.

Installed Fire Alarm Proposed Amount

\$144,437